

Mike's Roofing & Siding Inc.

11917 Winterpock Road, Chesterfield, VA 23838

Office: (804) 739-7364 | Fax: (804) 7390146 | Cell: (804) 400-2764

Email: Mike@MikesRoofingandSiding.com

PROPOSAL SUBMITTED TO:

Carson Compton

576 Rocky First Road, Blanktown 23059

Home: +1 (776) 126-9371 | Mobile: +1 (788) 778-8825 | Work: +1 (498) 639-1854

We hereby propose to furnish the materials and labor necessary for the completion of:

1. We will use tarps to protect decks and shrubbery from debris (when necessary). Ladder standoff device will be used to protect gutters.
Please remove all vehicles from driveway, and any items from the porches/decks.
Note: If you have skylights, we recommend plastic for dust and debris.
2. Plastic should be placed in attic to collect dust and debris, especially when installing ridge vents. (We can provide this service for additional fee.)
3. Remove existing shingles, felt, and nails on entire house.
4. Inspect roof deck for damaged plywood, replace Osb at \$60/sheet and Cdx plywood at \$70/sheet. 1.x sheathing boards \$5 per foot. This additional cost is not reflected inside this quote because damaged plywood/decking is not visible until after the roofing system (shingles, metal, etc) is removed.
5. We install the Integrity Roof System: supply & install Winterguard ice & water shield (sand finished) leak barrier 3' to 6' at all eaves per code, and in valleys and around skylights, chimneys, vent pipes and low sloped roofs under 4/12 pitch.
6. Supply and install Certainteed Synthetic Roof Runner underlayment with button caps (Diamond Deck is available if requested for an additional amount)
7. Supply and install SwiftStart starter shingles at eaves and rakes, new shingles and Shadow Ridge ridgecaps with roofing nails. Material is warranty by manufacturer. Homeowner will receive copies. 6 nails per shingle & 130 mph wind warranty on Landmark (15 year).
8. Ultimate Lifetime Collars Included. (Unless the use of standard collars are requested in options sections below.)
9. Close cut valleys with WinterGuard ice & water shield (sand finished) and 12" aluminum flashing.
10. Supply and install new aluminum wall flashing. Does not include siding repairs (if needed).
11. Supply and install new flashing around brick chimneys & skylights
12. Clean up job site, gutters, and dispose of all debris. We will use a magnet sweeper to pick up nails and reinstall gutter guards as needed.
13. All left over material after the job has been completed belongs to Mike's Roofing and Siding, Inc. and will be removed.

Mike's Roofing & Siding Inc.

11917 Winterpock Road, Chesterfield, VA 23838
 Office: (804) 739-7364 | Fax: (804) 7390146 | Cell: (804) 400-2764
 Email: Mike@MikesRoofingandSiding.com

Shingle Options (Select Option & Write Color)

| | | | | |
|----------|--|---------|--------------|--|
| Yes / No | CertainTeed Landmark (Lifetime LTD Warranty) | (color) | \$361,119.68 | |
| Yes / No | CertainTeed Landmark Pro (Lifetime LTD Warranty) | (color) | \$364,829.68 | |

Additional Options (Please Circle Options Wanted)

| | | | | |
|----------|--|--|----------------|--|
| Yes / No | Supply & install CertainTeed filtered Shingle-Over Ridge Vent | | \$4,558.00 | |
| Yes / No | Supply & install Velux Low E & UV glass skylight(s) with Velux Flashing Kit(s) | | \$46,078.20 | |
| Yes / No | Supply and install drip edge at eaves | | \$152.11 | |
| Yes / No | Supply and install drip edge at rakes | | \$894.11 | |
| Yes / No | Thermostatic roof fan (Homeowner responsible for electrical connections) | | \$72,191.30 | |
| Yes / No | Replace B vent base hotwater / gas vent or paint it | | \$3,510.72 | |
| Yes / No | Supply and install roof vent for bathroom exhaust fan | | \$40,693.40 | |
| Yes / No | Remove and reinstall J-Channel/Siding for new wall flashing and kickout flashing | | \$100,276.00 | |
| Yes / No | Optio ut aspernatur iusto quia blanditiis omnis obcaecati minima tempor atque maxime doloribus incididun | | \$130.38 | |
| Yes / No | Dolore illum in ut dolore est quibusdam cumque culpa | | \$40.28 | |
| Yes / No | Minus sequi rerum totam id qui voluptatem Porro incididunt id irure expedita dolor quam | | \$554.38 | |
| Yes / No | Nesciunt nihil nihil voluptate assumenda est anim modi aspernatur soluta consequatur doloremque magnam q | | \$986.86 | |
| Yes / No | Corrupti est illo ut nesciunt in | | \$747.30 | |
| Yes / No | Asperiores odio praesentium ea omnis | | \$944.46 | |
| Yes / No | Non adipisci at voluptates adipisci nesciunt architecto ad quis eos libero vel | | \$289.38 | |
| Yes / No | Qui debitis voluptas excepteur qui laudantium rerum cupidatat libero pariatur Quisquam sapiente facilis | | \$276.66 | |
| Yes / No | Maxime minim laborum Qui dolor id commodo distinctio Velit atque | | \$505.62 | |
| Yes / No | Id est quae facere qui anim consequat Et qui facilis ullamco nihil qui dolores quaerat proident modi | | \$849.06 | |
| | | | | |
| | Due to uncertainties in the supply chain, prices are subject to change. | | | |
| | Customers will receive notice of any pricing changes before work begins. | | Project Total: | |

In order to move forward, please select color and send back a signed copy of this document.

Acceptance of Proposal

All material is guaranteed to be as specified, and the above work to be performed in accordance with codes and specifications and completed in a workmanlike manner.

We recommend that you inspect your attic for moisture. We are not responsible for any mold issues.

PAYMENT: PAID IN FULL UPON COMPLETION

05/22/2026

2026-06-21

Customer Signature & Date

Today's Date

Price Good Until